

Bijoy Krishna Girls' College, Howrah
A NAAC B++ Accredited, NCTE Approved College with CPE Status
5/3, M.G. Road, Howrah-711101, WB

Ref. No...Quotation

Date...21/06/2016

NOTICE

Sealed Quotations are invited from Bonafide vendors for renovation of Two Nos Class Rooms at 1st Floor Adjacent to Duke Hall of Our college within seven days to the college office. The estimate are as follows-

SL No	DESCRIPTION OF WORK	QUANTITY	RATE
1.	Striping of worn out plaster and racking out joints of Wall, Ceiling etc. up to any height and to lead up to 75mm..... Item -10, Page-8	170.17 M ²	Rs.19/- Sq.m.
2.	Plaster to (Wall, Floor, ceiling) with Sand cement mortar 1:4, 15mm th for ceiling up..... Item 2(ii) (b) , Page-151	45.18 M ²	Rs.171/ M ²
3.	Plaster to (Wall, Floor, ceiling) with Sand cement mortar 1:6 , 20mm th for ceiling up..... Item 2(i) (b) , Page-151	124.98 M ²	Rs.174/ M ²
4.	Acrylic Distemper to Interior Wall , ceiling up etc, with a coat of solvent base interior grade acrylic primer (As per Manufacturer specification) including cleaning and smoothening of surface (Two Coats) Item-10, Page-157	340.34 M ²	Rs.76/ M ²
5.	Priming one coat on timber surface with synthetic oil bound primer of approved quality including smoothening the surface by sand papering etc. Item 7(a), page-162	67.20 M ²	Rs.41/ M ²
6.	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand paper etc. including using approved putty etc, in the surface if necessary. Item No-8(A)(a)(iv), Page-162	67.20 M ²	Rs.89/ M ²
7.	Ordinary cement concrete (mix 1: 1½:3) With graded stone chips 20 mm nominal size excluding shutter up a. Pakur variety Item – 7(b), Page-14	0.75 M ³	5216/ M ³
			Total
			Say
	Rupees Sixty Nine Thousand One Hundred Seventy Seven Only.		

Dr. Ruma Bhattacharyya
Principal, Bijoy Krishna Girls' College, Howrah